

Installation instructions

1. Assign a device location considering the space requirements (impact area). Slide direction recommended: north-east or in half-shade of trees.
2. Excavate soil for foundations, according to drawing.
Please note: To achieve maximum stability and a safe installation, a moderate level of soil solubility is required.
3. Pour in a drain layer of gravel of approx. 10 cm thickness between the bottom of the posts and plain base of foundation.
4. Insert reinforcing steel into the corresponding holes of the posts.
5. Place posts type A according to the corresponding number (see foundation layout) into the respective foundation hole.
Play level mark (=aluminium blind rivet) complies with the installation depth. Align every post by means of the play level mark facing into the same direction (see detail or foundation layout).

6. For installation of the pre-assembled components and/or single parts, the screws slightly have to be lubricated with installation paste!

Screw together platforms and posts by using the middle hole in the mounting brackets.

Tighten all screws after having aligned all components.

Install the slide exit with an inclination of 5° in sliding direction.

Screw connections see details in attached list.


We recommend not to insert the protection caps enclosed before first maintenance as they are only suitable for one-time use (see description in item No. 9).

7. Grout foundations with compressed concrete C20/25, chamfer and round off the edges, cover the foundations with a surface which meets the requirements for impact attenuation so that its critical fall height is equal to or greater than the maximum free height of fall of the equipment (acc. to EN 1176-1). The run-out section fall zone must have surfacing with a critical fall height of at least 1000 mm (acc. to EN 1176-3).
8. Release for play after concrete foundations have set.
9. According to maintenance instructions, check all screw connections after 4-5 weeks and retighten, if necessary.
Afterwards cover the screw heads with protection caps as follows: Insert grey protection caps into the countersunk drills (e.g. for platforms). The non-countersunk drills (e.g. for railings or a slide) have to be covered with the red protection caps by placing them onto the base part. Strongly pound them (e.g. by using a plastic mallet) until they audibly snap into the base part groove.


Please ensure that all special tools supplied (e.g. Allen key for secured Allen screws etc.) and all specific documents which are or may be useful for safety management acc. to EN 1176-7 (e.g. invoice, delivery note, order acknowledgement, installation instructions, maintenance instructions) are forwarded to the persons responsible.

**Necessarily insert all attachment parts before tightening the screws.
It is NOT possible to insert them afterwards.**


Mounting hints for platforms



View



View



Installation

0-22530-701
 Play structure

Scale 1:50
 Date 07.07.2020 EB

Page 2




Standard:	EN 1176
-----------	---------

Foundation details


www.kaiser-kuehne.com Tel. +49 42 54 / 93 15-0

© Kaiser & Kühne Freizeitgeräte D-27324 Eystrup

K & K Installation



Foundation plan



Installation

Standard:


0-22530-701
Play structure

Scale
1:50

Date
07.07.2020 EB

Page
4

Top view & impact area



Installation

Standard: EN 1176


0-22530-701
Play structure

Scale
1:50


Date
07.07.2020 EB

Page
5

Front view



Legend



dimension mark - total height of the equipment

dimension mark - maximum free height of fall

Installation


Standard:	EN 1176
-----------	---------


0-22530-701
Play structure


Scale
1:50

Date
07.07.2020 EB

Page
6

item no.	quantity	description	image
	1	set of (10 pcs.) laminated Robinia posts with stainless steel tubular pedestal with bottom cut-outs and protective post cap ES120 / red RAL 2002	
1200000	1	square platform 0,80 m x 0,80 m	
1200017	2	trapezoid platform 0,80 m/1,60 m	
1210358	4	bowed guardrail 0,80 m	
1210023	1	tandem guardrail 1,60 m	
1210198	1	timber balustrade 0,80 m x 0,70 m	

item no.	quantity	description	image
1210083	1	timber balustrade 0,80 m x 0,75 m	
1210199	1	timber balustrade 0,80 m x 0,90 m	
1230185	1	climbing wall (0,80) HPL red	
1210359	4	horizontal bar/ladder rung 0,80 m	
1210047	2	vertical climbing handle (0,60 m)	
1230099	1	climb up ramp 0,80 m platform height 1,00 m	

item no.	quantity	description	image
1230282	1	sloping monkey bars 0,80m x 2,40m	
041421001	1	K&K Trough-shaped attachment slide (2,00)	
1292058	1	fastening kit for 022530500	

Item: **022530701**

Order:


1294100

Play structure

Location:


Building Project:

12 x SFRS1200001 Platform at Robinia post, nut is platform-sided




per SC	Total	K&K-Item	Marking
1 x	12 x	3430129	Washer Ø 14 DIN1440 A2
1 x	12 x	3430021	Lock nut M12 DIN985 A2
1 x	12 x	3300016	Grey domed plastic cover cap SL 36 G
1 x	12 x	3400700	Hexagon head screw M12 x 120 DIN931 A2 with screw security coating/FGB red

42 x SFRS1210001 Standard bolting of barriers, handrails, slides to Robinia posts




per SC	Total	K&K-Item	Marking
1 x	42 x	3300054	red protective screw cap - lower part, domed M12
1 x	42 x	3300055	red protective screw cap - upper part, domed M12
1 x	42 x	3430025	Washer Ø 13 DIN125 A2
1 x	42 x	3400702	Hexagon head cap screw M12 x 160 DIN931 A2 with screw security coating FGB red

8 x SFRS1230004 Standard bolting of climbing poles, ramps etc. to Robinia posts with countersunk holes



per SC	Total	K&K-Item	Marking
1 x	8 x	3300016	Grey domed plastic cover cap SL 36 G
1 x	8 x	3430129	Washer Ø 14 DIN1440 A2
1 x	8 x	3400701	Hexagon head cap screw M12 x 130 DIN931 A2 with screw retention coating/FGB red

1 x SFAS1070006 Slide run-out section (up to 2,00 m) on foundation stone bolt assembly



per SC	Total	K&K-Item	Marking
2 x	2 x	1070365	Set of stone bolts for slide run-out section M12x160

Item: **022530701**

Order:

1294100

Play structure

Location:

Building Project:

10 x SFES1270007 Reinforcing steel for tubular pedestals



per SC	Total	K&K-Item	Marking
1 x	10 x	2130000	Reinforcing steel Ø 10 x 310 DIN 488

1 x SFWZ0000012 Lubricating metal (30g box) incl. brush



per SC	Total	K&K-Item	Marking
1 x	1 x	5300039	Lubricating metal box 30g
1 x	1 x	5200026	Brush for lubricating metal