



1. Assign location of equipment considering the space requirement.
2. Excavate soil for foundations according to drawing. Please note: To achieve maximum stability and safe installation, a moderate level of soil solubility is required.
3. Put steel posts into the foundation holes. Play level mark complies with the installation depth.
4. Grout foundations with compressed concrete C20/25, chamfer and round off the edges and cover with a surface which meets the requirements for impact attenuation so that the critical height of the surfacing shall be equal to, or greater than, the free height of fall of the equipment (acc. to EN 1176-1). Release for play after the concrete foundations have set.

Please ensure that all special tools (e.g. Allen key for secured Allen screws etc.) and all specific documents which are or may be useful for a safety management (e.g. invoice, delivery note, order acknowledgement, installation instructions, maintenance instructions) are forwarded to the persons responsible .

