



1. Assign location of equipment considering the space (falling space) requirements.
2. Excavate soil for foundation, according to drawing.
Please note: To achieve a maximum of stability and a safe installation a normal level of soil solubility is required.
3. Grout in foundation with compressed concrete C20/25, insert foundation anchorage into concrete 0,40 m below playlevel according to drawing and align with spirit level.
Insert foundation anchorage into concrete **at same level with top edge of foundation** (see detail).
4. After concrete foundation has set fix equipment to foundation anchorage in following order:
Flange of bearing - washer - self-locking domed cap nut M16.
5. Check all screw connections according to maintenance instructions after 4-5 weeks and screw down again if necessary.

Please take care that all special tools (e.g. special Allen key for secured Allen screws etc.) and all specific documents which are or may be useful for a safety management (e.g. invoice, delivery note, order acknowledgement, installation instructions, maintenance instructions) are forwarded to the responsible persons.