



1. Assign location of equipment considering the space requirement
2. Excavate soil for foundation, water drain pipe and seepage according to drawing.
3. Grout in foundation with compressed concrete PG75.
4. Put water valve into drain pipe and foundation according to drawing
- 5.. Release for play after foundation have set.